

Ringgold County Board of Supervisors Minutes May 26, 2020

The Ringgold County Board of Supervisors met in regular session Tuesday, May 26, 2020. The meeting was called to order at 9:00 A.M with the following members present: Kraig Pennington and Lyle Minnick. Ron Landphair joined via conference phone.

A motion was made by Pennington, second by Minnick to approve the agenda.
AYES: Unanimous NAYS: None

Assistant Engineer Jared Johnson met with the Board to provide secondary roads updates. The crew removed the existing rock from the roadway surface and began stripping topsoil from the 240th street project site. All but the Northwest half of the project was stripped, Johnson said. All culverts required for the project were hauled to the site. The middle 24" culvert was installed as well. It is planned to begin grading this week pending weather conditions.

The last of the spot rock was hauled last week finishing up the Northwest, Southwest and Southeast territories.

Materials were gathered for the upcoming Rice 20 bridge replacement project.

Johnson reported mowing started last week. Mowers started up in the Northwest part of the county. Once the ditches dry the crew will be finishing up with J23 and moving east towards Tingley.

Work order update:

WO 613 & 615: Ditch and clear brush along 190th Street between 270th Ave. and 280th Ave. (W.O. 613). Brush and ditched material is to be used for fill material at pipe replacement (W.O. 615). Replace existing damaged boiler pipe with new 48" ADS. Flume water to existing natural flow line. Place revetment at flume. FEMA culvert replacement. (In Progress)

WO 581: Replace existing deteriorated and separated 36" concrete culvert with new 42" x 60' ADS culvert. Place revetment and broken concrete pipes at outlet. Located on 110th Ave. south of 320th Street. (In Progress)

The preconstruction meeting for the NRCS EWP project was held on Thursday May 21 at the Engineer's office. At the meeting the particulars of the project were discussed along with what would and would not be allowed during construction. The contractor plans to begin once conditions are suitable to work. Their expectations are to begin sometime in June.

The department has prepared the concept statement for the Redding weir project and once an official project number is assigned the concept statement will be submitted, Johnson said.

The department received final easement plats for proposed ROW and TCE, and began preparing easement documents for the Washington 20 project. The department will continue developing the plan set.

Johnson reported there is no official preconstruction meeting date is set at this time for the Routh Box project. The department is considering holding the preconstruction meeting in the middle of June and will discuss with Interim Engineer Todd Hagan.

The crew began gathering materials for falsework on the Rice 20 project.

With regard to the pavement marking project, work is planned to begin June 1st pending weather. All no passing signs have been installed. There are several existing no passing signs, which do not meet reflectivity requirements and will be replaced. The department will be out this week finishing up laying out the pavement markings and will continue this process.

The Board met with Josh Keul with Keul Electric to discuss the location of the new generator for the courthouse. Based on size, the proposed location is a conflict as the cost of the project would exceed the proposed budget due to the relocation of sidewalk and added concrete work. Auditor Waske will work with Interim Engineer Don Staley to determine adequacy of the proposed location.

Landphair excused himself from the meeting at 10:30 a.m.

The Board reviewed claims that were paid Wednesday, May 20, 2020.

RESOLUTION RC20-114

WHEREAS, the Ringgold County Board of Supervisors do hereby approve the claims that were paid Wednesday, May 20, 2020.

THEREFORE, a motion was made by Kraig Pennington and seconded by Lyle Minnick stating such.

The vote on the resolution: AYES: Unanimous. NAYS: None.

ATTEST: Amanda Waske, Auditor. Passed and approved May 26, 2020.

A motion was made by Pennington, second by Minnick to approve the May 18, 2020 minutes and todays minutes. Motion carried.

There was no further business. A motion was made by Pennington and seconded by Minnick to adjourn the meeting at 10:50 a.m.

ATTEST: 
Board of Supervisors


Ringgold County Auditor